SHIMOGA DIVISION.

572

Dated 18th December 1918.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 22nd January 1919, for constructing masonry aqueducts for the High Level Channel under Sowlanga Tank, Honnali Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1919.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M. and 5 P.M., on all working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees three hundred and fifty in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for constructing masonry aqueducts for the High Level Channel under the Sowlanga Tank, Honnali Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Northern Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Constructing aqueducts for the High Level Channel of Sowlanga new Tank, Honnali Taluk.

Items of work	Per	Quantity
Excavating foundation	C. yd.	180
Filling up foundation with surki metal concrete	C. ft.	1,232
Burnt brick in surki mortar	"	7,888
Arch work burnt brick in surki mortar	S. ft.	1,430
Burnt stone slabs 4½" thick dressed and fixed	"	1,703
Plastering with surki mortar	Sq.	65·29
Cement pointing	"	7·65
Temporary centering of reserve wood sand bags setting and removing	Lump	sum Rs.
Approach embankment clearing thorning jungle and entirely grubbed up with routs ..	S. yd.	3,520
Preparing ground by picking 9" deep to receive fresh earth ...	"	4,840
Excavating trenches on either side at the toe and in centre of embankment and puddling with good earth.	C. yd.	330
Filling up earth in consolidation half the quantity from the approach clearing at the down stream and half from a distance of ¼ mile earthwork.	"	5,670
Revetment work	"	390
Pointing with concrete	Sq.	5·00
Jungle wood centering, fixing and removing	Lump	sum Rs.
Clearing the approaches at the rear of the aqueduct	Lump	sum Rs.

K. NARAYANA IYENGAR,
Offg. Executive Engineer.

CHITALDRUG DIVISION.

Abstract Notification.

The attention of the public is invited to page 1113, Part IV of the *Mysore Gazette*, dated 19th December 1918, calling for tenders for restoring Kalgere tank Registered No. 60 of Baramasagara hobli, Chitaldrug Taluk, Chitaldrug District.

The last date up to which the tenders will be received is 4th January 1919.

N. G. KRISHNA IYENGAR,
Executive Engineer.

BHADRA ANICUT RANGE.

Abstract Notification.

The attention of the public is invited to the Notification dated 11th December 1918, in pages 1114 and 1115 of Part IV of the *Mysore Gazette*, wherein tenders for constructing an anicut across the river Bhadra near Gopala has been called for.

V. K. KUNTE,
Temporary Engineer, Gopala Anicut Range, Benkipur.